

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-20945-00-00
Spot: N2NWSE Sec/Twnshp/Rge: 27-14S-13W
2310 feet from S Section Line, 1980 feet from E Section Line
Lease Name: LETSCHE Well #: 14
County: RUSSELL Total Vertical Depth: 2400 feet

Operator License No.: 5184
Op Name: SHIELDS OIL PRODUCERS INC
Address: 326 N MAIN
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	255		180 SX
PROD	4.58	2389		100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/12/2012 9:30 AM
Plug Co. License No.: 33385 Plug Co. Name: J & M WELL SERVICING, INC.
Proposal Rcvd. from: MICHAEL A. MCGLOCKLIN Company: SHIELDS OIL PRODUCER Phone: (785) 483-3141

Proposed Plugging Method:
Ordered 250 sx 60/40 pozmix - 4% gel
300 # hulls

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/12/2012 4:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 2200'. Pumped 75 sx of cement w/150 # hulls.
Pulled tubing to 1000'. Pumped 90 sx of cement w/150 # hulls.
Cement circulated.
POOH and hooked to braden head. Pumped 25 sx of cement.
Cement circulated out the casing.

Perfs:

Top	Bot	Thru	Comments
2327	2330		
2311	2314		

Remarks: ALLIED CEMENTING INC. TICKET # 56385

Plugged through: TBG

RECEIVED
APR 19 2012
KCC WICHITA

5/14/12

District: 04

Signed

Ray A. Dinkel

(TECHNICIAN)

CM

APR 16 2012