

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-00442-00-00
Spot: SESWSE Sec/Twnshp/Rge: 33-15S-12W
330 feet from S Section Line, 1650 feet from E Section Line
Lease Name: KAUFMAN Well #: 1(2)
County: RUSSELL Total Vertical Depth: 3318 feet

Operator License No.: 9390
Op Name: SCHREIBER, MARY ANN DBA SCHREI
Address: 598 2ND AVE
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8	195		
PROD	5	3314		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/27/2012 7:30 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: RICK SCHREIBER Company: SCHREIBER OIL Phone: (620) 793-2032

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix - 4% gel
10 sx of gel
500# hulls

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/27/2012 1:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforated @ 1500', 800' and 450'.
Ran tubing to 3010'. Pumped 10 sx gel follow w/ 50 sx of cement w/100 # hulls.
Pulled tubing to 1520'. Pumped 75 sx of cement w/200 # hulls.
Pulled tubing to 810'. Pumped 90 sx cement w/200 # hulls.
Cement circulated.
POOH and hooked on. Pumped 30 sx of cement at 250 psi.
Hooked to Braden head and pressured to 350 psi.

Perfs:

RECEIVED
APR 19 2012
KCC WICHITA

Remarks: COPELAND CEMENT AND ACID

Plugged through: TBG

District: 04

Signed

Ray A. Dinkel

(TECHNICIAN)

CM

APR 16 2012

Form CP-2/3

5/14/12