

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-05372-00-00
Spot: NWSESE Sec/Twnshp/Rge: 33-15S-12W
990 feet from S Section Line, 990 feet from E Section Line
Lease Name: KAUFMAN Well #: 1
County: RUSSELL Total Vertical Depth: 3318 feet

Operator License No.: 9390
Op Name: SCHREIBER, MARY ANN DBA SCHREI
Address: 598 2ND AVE
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8	340		
PROD	5	3316		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/28/2012 7:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: RICH SCHREIBER Company: SCHREIBER OIL Phone: (620) 793-2032

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix - 4% gel
10 sx gel
500# hulls

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/28/2012 12:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

Perforated at 1500', 800' and 450'.
Ran tubing to 2973'. Pumped 10 sx of gel followed w/50 sx of cement w/100 # hulls.
Pulled tubing to 1500'. Pumped 75 sx of cement w/200 # hulls.
Pulled tubing to 810'. Pumped 110 sx of cement w/100 # hulls.
Cement circulated.
POOH and hooked to casing. Pumped 20 sx of cement at 250 psi. Shut in pressure at 250 psi.
Hooked to braden head and pumped 20 sx of cement at 350 psi.

RECEIVED
APR 19 2012
KCC WICHITA

Remarks: COPELAND CEMENT AND ACID

Plugged through: TBG

District: 04

Signed

Ray Dinkel

(TECHNICIAN)

cm

APR 16 2012

Form CP-2/3

5/14/12