

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-155-21007-00-01  
Spot: NESWNESW Sec/Twnshp/Rge: 9-26S-4W  
1928 feet from S Section Line, 3442 feet from E Section Line  
Lease Name: HARP Well #: 1-A  
County: RENO Total Vertical Depth: 4606 feet

Operator License No.: 5822  
Op Name: VAL ENERGY, INC.  
Address: 200 W DOUGLAS AVE STE 520  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	295		200 SX
PROD	5.5	4590	508	100 SX

Well Type: GAS UIC Docket No: Date/Time to Plug: 06/20/2011 12:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: Phone: (620) 562-8088

Proposed Plugging Method: PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL  
Date/Time Plugging Completed: 07/04/2011 12:00 AM KCC Agent: B. J. HOPE

Actual Plugging Report:

CASING WAS PARTED @ 500' - PULLED CASING BEFORE NOTIFYING KCC. RAN VIDEO CAMERA DOWN HOLE TO 376' - BIG HOLE. 6-27-11 RAN IN WITH 800' TUBING PUMPED 100 SX COMMON CEMENT WITH 3% CC. BENT 10 JTS ABOUT 310' FEET OF TUBING COMING OUT OF HOLE. TAGGED UP @ 508'. SPOTTED ANOTHER 100 SX - 3% CC. CEMENT @ 500'. 6-28-11 RAN TUBING INTO 350' - PUMPED 380 BARRELS OF DRILLING MUD CAPPED WITH 120 SX COMMON CEMENT & 3% CC. 6-30-11 DROPPED 36 YDS OF SAND - TAGGED AT 530'. 7-1-11 DROPPED 96 YARDS OF SAND TAGGED @ 465'. 7-2-11 DROPPED 145 YARDS OF SAND TAGGED @ 350'. 7-5-11 RAN TUBING INTO 340' FEET CAPPED SAND WITH 50 SX CEMENT WITH 3% CC. RAN TUBING TO 207' FEET CIRCULATED TO SURFACE 125 SX COMMON CEMENT.

Perfs:

RECEIVED  
APR 19 2012  
KCC WICHITA

Remarks: COPELAND CEMENT OUT OF GREAT BEND. PARTED CASING IN OLD SWD CHANGED TO GAS WELL.

Plugged through: TBG

District: 02

Signed

B. J. Hope

(TECHNICIAN)

5/14/12  
Form CP-2/3