

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-22804-00-00
Spot: NESENW Sec/Twnshp/Rge: 32-15S-11W
3630 feet from S Section Line, 2970 feet from E Section Line
Lease Name: BORELL C Well #: 4
County: RUSSELL Total Vertical Depth: 3386 feet

Operator License No.: 31086
Op Name: RICHLAN DRILLING, A GENERAL PAR
Address: 598 2ND AVE
BEAVER, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	496		250 SX
PROD	5.5	3386		125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/29/2012 9:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: RICK SCHREIBER Company: D S & W WELL SERVICING, INC. Phone: (620) 793-2032

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% Gel. 10 sx Gel. 500# hulls.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/28/2012 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1500', 750' and 450'.
Ran Tubing to 3020'. Tied to tubing.
Pumped 10 sx gel followed w/50 sx cement and 100# hulls.
Pulled tubing to 1500' and pumped 75 sx cement w/100# hulls.
Pulled tubing to 800'.
Circulated cement to surface in casing and surface pipe w/120 sx cement and 100# hulls.
POOH. Topped off w/5 sx cement.

Perfs:

Remarks: COPELAND ACID AND CEMENTING

Plugged through: TBG

RECEIVED
APR 19 2012
KCC WICHITA

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM

APR 12 2012

Form CP 2/3

5/11/12