

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-03153-00-00
Spot: NENWSW Sec/Twnshp/Rge: 30-16S-11W
2310 feet from S Section Line, 990 feet from W Section Line
Lease Name: SO OESER TWIN Well #: 10
County: BARTON Total Vertical Depth: 3269 feet

Operator License No.: 4871
Op Name: CURT-S OIL OPERATIONS LLC
Address: PO 8
GREAT BEND, KS 67530

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| SURF | 8.625 | 400 | | |
| PROD | 5.5 | 3260 | | |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/11/2012 2:00 PM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: CURTIS HITSCHMANN Company: D S & W WELL SERVICING, INC. Phone: (620) 793-2540

Proposed Plugging Method:
Ordered 350 sx 60/40 pozmix 4% gel.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/11/2012 4:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Ran tubing to 2650'. Pumped 100 sx cement
Pulled tubing to 1500'. Pumped 75 sx cement
Pulled tubing to 800'. Circulated cement to surface w/50 sx cement
Puffed tubing topped of w/ 5 sx cement.
Tied to surface pipe pumped 40 sx cement pressured to 200 psi shutin.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|-----------|
| 3199 | 3216 | | LKC I & J |
| 3130 | 3142 | | LKC G |

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

RECEIVED
APR 23 2012
KCC WICHITA

APR 13 2012

Form CP-2/3

5/07/12