

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-03148-00-00  
Spot: NWNWSW Sec/Twnshp/Rge: 30-16S-11W  
2310 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: SO OESER Well #: 5  
County: BARTON Total Vertical Depth: 3292 feet

Operator License No.: 4871  
Op Name: CURT-S OIL OPERATIONS LLC  
Address: PO 8  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	400		
PROD	5.5	3293		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/30/2012 8:00 AM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: CURTIS HITSCHMANN Company: D S & W WELL SERVICING, INC. Phone: (620) 793-2540

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix - 4% gel w/600 # hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/30/2012 4:00 PM KCC Agent: BRUCE RODIE

**Actual Plugging Report:**

Junk in hole at 2187'. Could not get through. Will plug from there.  
Ran tubing to 2187'. Tied to tubing, pumped 125 sx cement w/300 # hulls.  
Pulled tubing to 1500'. Pumped 75 sx cement w/200 # hulls.  
Pulled tubing to 500'. Pumped 50 sx cement, circulated cement out casing.  
Pulled tubing, tied to casing, pumped 25 sx cement down surface.

**Perfs:**

Top	Bot	Thru	Comments
3254	3260		LKC K
3222	3229		LKC J
3206	3216		LKC I

RECEIVED  
APR 23 2012  
KCC WICHITA

Remarks: COPELAND ACID AND CEMENTING.

Plugged through: CSG

District: 04

Signed Bruce Rodie  
(TECHNICIAN) CM

APR 16 2012

Form CP-2/3  
✓ 5/09/12