

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-02099-00-00  
Spot: SESWNW Sec/Twnshp/Rge: 30-16S-11W  
2970 feet from S Section Line, 4290 feet from E Section Line  
Lease Name: NORTH OESER Well #: 9  
County: BARTON Total Vertical Depth: 3273 feet

Operator License No.: 4871  
Op Name: CURT-S OIL OPERATIONS LLC  
Address: PO 8  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	470		
PROD	5.5	3269		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/27/2012 4:00 PM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: CURTIS HITSCHMANN Company: CURT'S OIL Phone: (620) 793-2540

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix - 4% gel  
600 # hulls

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/27/2012 7:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Junk in hole at 1528'. Could not get through.  
Will plug from there.  
Ran tubing to 1528'. Tied to tubing. Pumped 90 sx cement.  
Pulled tubing to 580'. Pumped 135 sx cement. Circulated out of casing.  
Pulled tubing. Topped off casing with 25 sx cement.  
Tied to surface. Pumped 85 sx cement pressured to 200 psi. Shut in.

Perfs:

Top	Bot	Thru	Comments
3082	3086		LKC B
3063	3067		LKC A
3054	3058		LKC A

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSG

RECEIVED  
APR 23 2012  
KCC WICHITA

District: 04

Signed Bruce Rodie  
(TECHNICIAN)

APR 16 2012

Form CP-2/3

5/07/12