

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-07416-00-01
Spot: NESWSENE Sec/Twnshp/Rge: 34-16S-12W
3011 feet from S Section Line, 888 feet from E Section Line
Lease Name: JENISCH Well #: 4
County: BARTON Total Vertical Depth: 3372 feet

Operator License No.: 4871
Op Name: CURT-S OIL OPERATIONS LLC
Address: PO 8
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	225		0 SX
PROD	5.5	3356		0 SX

Well Type: SWD UIC Docket No: D20786.0 Date/Time to Plug: 04/12/2012 9:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: CURTIS HITSCHMANN Company: GRESSEL OILFIELD SERVICE, LLC Phone: (620) 793-2540

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix - 4% gel w/400 # hulls. 10 sx gel

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/04/2012 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

Perfed at 1500', 850' and 200'
Ran tubing to 3335'. Pumped 10 sx gel followed with 75 sx cement and 100 # hulls.
Pulled tubing to 1524'. Pumped 70 sx cement w/ 200 # hulls.
Pulled tubing to 851'. Circulated cement to surface w/ 200 sx cement
Pulled tubing. Topped off with 25 sx cement
Tied to surface pipe. Pumped 15 sx cement. Pressured to 200 psi. Shutin.

RECEIVED
APR 23 2012
KCC WICHITA

Remarks: COPELAND ACID AND CEMENTING

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN) CM

APR 18 2012
APR 13 2012

cc to WIC 4/26/12

5/07/12