

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-24626-00-00  
Spot: NESWNESE Sec/Twnshp/Rge: 36-13S-20W  
1832 feet from S Section Line, 938 feet from E Section Line  
Lease Name: ERNEST PFEIFER Well #: D-2  
County: ELLIS Total Vertical Depth: 3970 feet

Operator License No.: 34347  
Op Name: BENCHMARK ENERGY LLC  
Address: PO BOX 8747  
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	257		160 SX
PROD	5.5	3964		475 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/19/2012 8:00 AM  
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC  
Proposal Rcvd. from: JERRY NASH Company: BENCHMARK ENERGY LLC Phone: (620) 672-1114

Proposed Plugging Method: Ordered - 350sacks 60/40 poz mix 4 % gel; 500# hulls  
Rods & tubing parted around 1250' -what came out was full of holes.  
Tried overshot. Nothing. Felt like on casing.  
Well was sqzd in salt section w/1000sxs cement  
Emergency plug with rig over hole.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/19/2012 10:15 AM KCC Agent: PAT STAAB

Actual Plugging Report:

4-18-2012 Perf Tech shot 2 hole perfs @ 820' & 250'  
Professional Pulling Services RIH with tubing to 1200'. Quality rigged to tubing & mixed & pumped 50 sacks cement neat, followed by 80 sacks with 500 # hulls mixed in.  
Pulled tubing. Quality rigged to 5.5" casing with a swedge & mixed & pumped 15 sacks with 500 # PSI & 500 # SIP.  
Rigged to 8.625" CSG & pumped 10 sacks to pressure with 200 # PSI & 200 # SIP.

Perfs:

Top	Bot	Thru	Comments
3914	3916		PF
3884	3889		PF
3883	3916		ARB

RECEIVED  
APR 23 2012  
KCC WICHITA

Remarks: QUALITY OIL WELL CEMENTING CO. TICKET # 373

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

*Pat Staab*  
(TECHNICIAN)

CM

APR 19 2012

✓ 5/09/12