

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-20267-00-00
Spot: N2SWSW Sec/Twnshp/Rge: 4-15S-13W
990 feet from S Section Line, 4620 feet from E Section Line
Lease Name: LETSCH B Well #: 6
County: RUSSELL Total Vertical Depth: 3367 feet

Operator License No.: 34506
Op Name: EMPIRE ENERGY E&P, LLC
Address: 380 SOUTHPOINTE BLVD #130
CANONSBURG, PA 15917

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3100		
SURF	8.625	839		450 SX
PROD	5.5	3364		350 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/19/2012 9:30 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: RICKY POPP Company: EMPIRE ENERGY, LLC Phone: (620) 786-5514

Proposed Plugging Method: Ordered 250 sx 60/40 pozmix - 4% gel and 200 # hulls.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/19/2012 4:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Cut casing @ 1550' leaving 1814' of 5 1/2 " casing in hole.
On 04/18/2012, sanded off bottom to 2975'.
On 04/19/2012, tagged sand and spotted 5 sx cement.
Cut casing @1550'.
Pulled casing to 1457', pumped 75 sx of cement w/200 # hulls.
Pulled casing to 878', pumped 25 sx of cement.
Pulled casing to 425', pumped 80 sx of cement.
Cement circulated.
POOH and topped of w/ 5 sx of cement.

Perfs:

Top	Bot	Thru	Comments
3308	3315		
3214	3217		
3112	3120		
3050	3068		
3039	3041		

RECEIVED
APR 23 2012
KCC WICHITA

Remarks: QUALITY CEMENTING - TICKET # 329

Plugged through: CSG

District: 04

Signed Ray A. Dinkel
(TECHNICIAN)

CM

APR 20 2012

Form CP-2/3
5/07/12