

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-189-21543-00-00  
Spot: NWSESE Sec/Twnshp/Rge: 1-32S-38W  
990 feet from S Section Line, 1250 feet from E Section Line  
Lease Name: CORNELL UNIVERSITY B Well #: 1  
County: STEVENS Total Vertical Depth: 6350 feet

Operator License No.: 32446  
Op Name: MERIT ENERGY COMPANY, LLC  
Address: 13727 NOEL RD STE 500  
DALLAS, TX 75240

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1754		WITH 560 SX CMT
PROD	5.5	6205	1978	WITH 310 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/22/2012 8:30 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: SET CIBP @ 5900' WITH 2 SX CMT. PLUG AT 1790' WITH 20 SX GEL & 50 SX CMT. PLUG AT 650' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: JACK MACLASKEY Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/22/2012 2:30 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

RIH W/CIBP, UNABLE TO GET BELOW 3125'. POOH W/CIBP & RIH W/TBG, STACKED OUT AT 3125'. PUMPED 50 SX CMT WITH GOOD CIRCULATION. SD. WOC. TAGGED TOP OF CMT AT 2673'. SHOT 5 1/2" CASING AT 2418'. UNABLE TO WORK FREE. RE-SHOT AT 1978'. POOH W/CSG. RIH W/TBG TO 1800' & PUMPED 80 SX CMT. PUMP 60 SX CMT AT 600'. PUMPED 20 SX CMT AT 60'.

Perfs:

Top	Bot	Thru	Comments
5956	5964		LOWER MORROW

RECEIVED  
APR 23 2012  
KCC WICHITA

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA 10 YR RULE\*\* USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed

Jack L MacLasky  
(TECHNICIAN)

RECEIVED  
MAR 29 2012  
KCC DODGE CITY

Form CP-2/3

5/07/12

BRAND