

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-067-00090-00-00
Spot: SW Sec/Twnshp/Rge: 36-29S-35W
1393 feet from S Section Line, 1315 feet from W Section Line
Lease Name: SCHWERTFEGER Well #: 1
County: GRANT Total Vertical Depth: 2740 feet

Operator License No.: 4824
Op Name: PIONEER NATURAL RESOURCES USA.
Address: 5205 N O CONNOR BLVD
IRVING, TX 75039

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	10.75	597		WITH 100 SX CMT
PROD	6.625	2531	0	WITH 125 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/10/2012 9:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: PERFORATE @ 1750'. RIH W/TBG TO 1700' & SPOT 125 SX CMT WITH 125# HULLS TO GET CMT ABOVE CASING LEAK AT 1500'. PERFORATE CASING AT 630' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/10/2012 1:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

****WELL HAS CASING LEAK @ 1500'.** TAGGED TOP OF FILL @ 1845'.
PERFORATED CASING @ 1835'. RIH W/TBG TO 1835' & SPOTTED 125 SX CMT
W/125# HULLS. WAIT ON CMT. TAGGED TOC @ 1400'. RIH W/TBG TO 1380' &
SPOTTED 25 SX CMT. PERFORATED CASING AT 630'. PUMPED 300 SX CMT
CIRCULATING CMT TO SURFACE.**

Perfs:

Top	Bot	Thru	Comments
2511	2735		

RECEIVED
APR 23 2012
KCC WICHITA

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed Jack MacLaskey
(TECHNICIAN)

RECEIVED
APR 18 2012
KCC DODGE CITY

Form GP-2/3
5/07/12