

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-00528-00-00
Spot: SWSWSWNE Sec/Twnshp/Rge: 1-30S-34W
2484 feet from N Section Line, 2509 feet from E Section Line
Lease Name: MOODY Well #: 1
County: HASKELL Total Vertical Depth: 2770 feet

Operator License No.: 4824
Op Name: PIONEER NATURAL RESOURCES USA.
Address: 5205 N O CONNOR BLVD
IRVING, TX 75039

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	10.75	656		WITH 300 SX CMT
PROD 7		2609	0	WITH 500 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/11/2012 1:00 PM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580)251-9618

Proposed Plugging Method: RIH W/TBG TO TOP OF FILL @ SPOT 125 SX CMT W/150# HULLS. WOC & PRESSURE TEST CASING. PERFORATE CASING AT 700' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/11/2012 5:30 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

****WELL HAS CASING LEAK @ 1406-1600'.** TAGGED TOP OF FILL AT 2600'. RIH W/TBG TO 2580' & PUMPED 30 SX GEL, 75 SX CMT W/150# HULLS. SDON. TAGGED TOC @ 2468'. RIH W/TBG TO 1750' & PUMPED 125 SX CMT W/100# HULLS. WOC. TAGGED TOC @ 1468'. RIH W/TBG TO 1450' & PUMPED 50 SX CMT. WOC. TAGGED TOC @ 1270'. PERFORATE CASING AT 700'. PUMPED 345 SX CMT CIRCULATING CMT TO SURFACE.**

Perfs:

Top	Bot	Thru	Comments
2727	2770		
2674	2701		
2628	2658		
2594	2622		
2572	2588		

RECEIVED
APR 23 2012
KCC WICHITA

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed

Jack MacLaskey
(TECHNICIAN)

RECEIVED

APR 18 2012

KCC DODGE CITY

Form CP-2/3

5/07/12

13007