

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-04681-00-00
Spot: NWNWNE Sec/Twnshp/Rge: 15-19S-12W
4950 feet from S Section Line, 2310 feet from E Section Line
Lease Name: SCHARTZ Well #: 2A
County: BARTON Total Vertical Depth: 3425 feet

Operator License No.: 5086
Op Name: PINTAIL PETROLEUM, LTD.
Address: 225 N MARKET STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	150		100 SX
PROD	5.5	3416		100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/26/2012 12:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: RICK POPP Company: POPP OPERATING Phone: (620) 786-5514

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix - 4% gel
500 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/27/2012 3:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Junk in hole at 300'. Drilled, milled and tried wash over pipe. Could not get past 374'. Will plug.
Ran 1" pipe to 374'. Stacked out.
Pumped 40 sx cement. Circulated out of casing.
Pulled tubing. Tied to casing. Pumped 5 sx cement pressured to 500 psi. Shut in at 350 psi.

Perfs:

Top	Bot	Thru	Comments
3163	3195		

RECEIVED
APR 23 2012
KCC WICHITA

Remarks: QUALITY OILWELL CEMENTING

Plugged through: CSG

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

CM

MAR 27 2012

Form CP-2/3

✓ 5/07/12