

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-055-20897-00-00  
Spot: SESWSWNW Sec/Twnshp/Rge: 10-25S-33W  
2855 feet from S Section Line, 4885 feet from E Section Line  
Lease Name: TAIT A Well #: 2  
County: FINNEY Total Vertical Depth: 3050 feet

Operator License No.: 5447  
Op Name: OXY USA INC.  
Address: 5 E GREENWAY PLZ PO BOX 27570  
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	869		WITH 311 SX CMT
COND	22	34		WITH 5 SX CMT
PROD	5.5	3049	0	WITH 396 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/11/2012 9:00 AM  
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.  
Proposal Rcvd. from: JOHN SCHOOLCRAFT Company: SARGENT LILLARD CASING PULL Phone: (580)254-1881

Proposed Plugging Method: SET CIBP @ 2785' WITH 2 SX CMT. CUT CASING AT FREE POINT. PLUG AT 1890' WITH 50 SX CMT. PLUG AT 1020' WITH 100 SX CMT. PLUG AT 510' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/12/2012 2:30 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

RAN WIRELINE WITH WEIGHT TO 2890'. RAN FLOAT ON WIRELINE. FLUID LEVEL @ 2500'. PUMP 250# HULLS & 25 SX CMT TO 2876'. TAG WITH WIRELINE. PUMP 20 SX CMT AT 1727'. TAGGED TOC @ 1250'. PLUG AT 1100' WITH 45 SX CMT. PLUG AT 550' WITH 30 SX CMT. PLUG AT 40' WITH 5 SX CMT. PUMP 30 SX CMT INTO ANNULUS. PRESSURED TO 500 PSI.

Perfs:

Top	Bot	Thru	Comments
2862	2876		
2850	2856		
2833	2844		

RECEIVED  
APR 23 2012  
KCC WICHITA

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA HIGH FL\*\* USED COMMON CEMENT BY SARGENT & LILLARD.

Plugged through: CSG

District: 01

Signed

Jack MacLaskey 4/5/12  
(TECHNICIAN)

RECEIVED

APR 18 2012

KCC DODGE CITY