

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-02189-00-01
Spot: SENENW Sec/Twnshp/Rge: 25-19S-12W
4290 feet from S Section Line, 3111 feet from E Section Line
Lease Name: PETZ Well #: 2
County: BARTON Total Vertical Depth: 3560 feet

Operator License No.: 3334

String Size Depth (ft) Pulled (ft) Comments

Op Name: ROBL-SIX, INC.

SURF 8.625 187

Address: 109 W 10TH ST

PROD 5.5 3372

ELLINWOOD, KS 67526

Well Type: SWD

UIC Docket No: D24793.0

Date/Time to Plug: 04/16/2012 2:00 PM

Plug Co. License No.: 6901

Plug Co. Name: D S & W WELL SERVICING, INC.

Proposal Rcvd. from: CRAIG ROBL

Company: ROBL SIX

Phone: (620) 564-3485

Proposed Plugging Method: Emergency plug rig over hole. Ordered 350 sx 60/40 pozmix - 4% gel cement, 600 # hulls, 12 sx gel.

Plugging Proposal Received By: CASE MORRIS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 04/16/2012 4:00 PM

KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

Perorated at 1450' and 650'.
Ran tubing to 2810'. Tied to tubing and pumped 12 sx gel followed by 75 sx cement w/250 # hulls.
Pulled tubing to 1450'. Tied to tubing. Pumped 100 sx cement w/350 # hulls.
Pulled tubing to 650'. Tied to tubing and circulated cement w/ 90 sx cement.
Pulled tubing. Topped off w/10 sx cement.
Tied to surface pipe. Pressured up. Did not take any cement.

RECEIVED
APR 23 2012
KCC WICHITA

Remarks: COPELAND ACID AND CEMENTING.

Plugged through: TBG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM

APR 19 2012

cc to KCC 4/26/12