

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-22624-00-00
Spot: W2E2E2NE Sec/Twnshp/Rge: 22-20S-6W
1320 feet from N Section Line, 600 feet from E Section Line
Lease Name: FRY Well #: 8
County: RICE Total Vertical Depth: 3100 feet

Operator License No.: 32381
Op Name: KREHBIEL, JAY DBA K & S OIL CO.
Address: 409 RANDOLPH
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	212		150 SX
T1	2.375	2980		
PROD	5.5	3099	2100	125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/27/2012 8:00 AM
Plug Co. License No.: 30280 Plug Co. Name: SUNFLOWER WELL SERVICE, INC.
Proposal Rcvd. from: BUD DAVIS Company: _____ Phone: (620) 654-8342

Proposed Plugging Method: ACCORDING TO STATE RULES AND REGULATIONS.

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 02/29/2012 9:00 AM KCC Agent: B. J. HOPE

Actual Plugging Report:

2/25/2012 - SANDED BACK TO 2840' CAPPED WITH 5 SX OF CEMENT. 2/27/12 CUT CASING OFF AT 2100' PULLED CASING TO 918' SPOTTED 35 SX CEMENT PLUG. PULLED CASING TO 490' SPOTTED 35 SX CEMENT PLUG. PULLED CASING TO 277' AND CIRCULATED TO SURFACE WITH 80 SX OF CEMENT. 2/29/12 CEMENT FELL 44' INSIDE SURFACE, FILLED WITH 5 SX OF COMMON CEMENT.

Perfs:

Top	Bot	Thru	Comments
3060	3064		
3035			
3004	3008		
2906	2910		

Remarks: ALLIED OUT OF RUSSELL WERE THE CEMENTORS. USED 60/40 4% POZ MIX

Plugged through: CSG

District: 02

Signed B. J. Hope

(TECHNICIAN)

RECEIVED
APR 25 2012
KCC WICHITA

5/10/12

JK