

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-00448-00-02  
Spot: NENENE Sec/Twnshp/Rge: 30-27S-10W  
4950 feet from S Section Line, 330 feet from E Section Line  
Lease Name: MILES A Well #: 1  
County: KINGMAN Total Vertical Depth: 4951 feet

Operator License No.: 3880

Op Name: KC RESOURCES, INC. DBA CRYSTAL RIVER

Address: P. O. BOX 6749  
SNOWMASS VILLAGE, CO 81615

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	10	2455		

*Handwritten initials*

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 10/06/2011 8:00 AM

Plug Co. License No.: 7023

Plug Co. Name: KLIMA WELL SERVICE, INC.

Proposal Rcvd. from: TOM ELLIOT

Company: KCC RESOURCES

Phone: (970) 309-2181

Proposed Plugging Method: 24" CASING @ 64', 20" CASING @ 89', 15.5" CASING @ 790', 12.5" CASING @ 1712', 10" CASING @ 2455', 8 5/8" CASING @ 2275' TO 3375'. PBD 3541'

Plugging Proposal Received By: JEFF KLOCK

Witness Type: PARTIAL

Date/Time Plugging Completed: 10/25/2011 4:00 PM

KCC Agent: B. J. HOPE

Actual Plugging Report:

Perfs:

10/5/11 DUG HEAD OUT NO CEMENT ON BACKSIDE (10-6-11) 50 SX CEMENT SPOTTED @ 3260 - TAGGED PLUG @ 2920' - PERFERATED CASING THEN SPOTTED 50 SX CEMENT @ 1760' - TAGGED CEMENT @ 1540' - PERFERATED 10" @ 330' PUMPED 100 SX - NO CEMENT TO SURFACE - USED TUBING INSIDE OF 10" - 10-10-11 RAN TUBING INTO 130' PUMPED 80 SX CEMENT RAISED CEMENT TO SURFACE, PUMPED 35 SX CEMENT DOWN BACKSIDE OF 10". RAISED CEMENT INSIDE 12", MOVED RIG OFF HOLE. 10-11-11 TRACK HOE DUG 18' TO GET TO TOP OF 24" CASING. 10/13/11 PUMPED 10 SX CEMENT DOWN BETWEEN 24" & 20" CASING. WELD BELL OVER 20" - 15.5" - 12.5" & 10" CASING. PUMPED 200 SX WITH NO RETURNS. 10-21-11 PUMPED 350 SX CEMENT INTO BELL - 2HOURS LATER PUMPED 150 SX CEMENT GOT CIRCULATION OUT OF 8 5/8 OFFSET HOLE. 10-25-11 CHECK CEMENT INSIDE BELL FELL 4 FEET, TOPPED OF WITH 5 SX CEMENT & WELD PLATE OVER CSG.

Remarks: DENIED TA - HIGH FLUID LEVEL & PARTIAL CASING - USED COMMON CEMENT WITH 2% CC ON CEMENT.

RECEIVED  
APR 25 2012  
KCC WICHITA

Plugged through: TBG

District: 02

Signed

*Handwritten signature*

(TECHNICIAN)

5/07/12

*Handwritten mark*