

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-21934-00-01
Spot: N2NENE Sec/Twnshp/Rge: 31-25S-34W
560 feet from N Section Line, 660 feet from E Section Line
Lease Name: GREATHOUSE Well #: 31 #1
County: FINNEY Total Vertical Depth: 5264 feet

Operator License No.: 5278
Op Name: EOG RESOURCES, INC.
Address: 3817 NW EXPRESSWAY STE 500
OKLAHOMA CITY, OK 73112

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4470		WITH 5 SX CMT
CIBP		5000		
SURF	8.625	1678		WITH 480 SX CMT
PROD	4.5	5254	1870	WITH 205 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 04/17/2012 1:00 PM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: SAUL NAVARRETE Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: CIBP @ 4484' & 5 SX CMT. PLUG AT 1900' WITH 120 SX CMT. PLUG AT 850' WITH 60 SX CMT. PLUG AT 64' WITH 20 SX CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/18/2012 5:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 4470 WITH 5 SX CMT. 1ST PLUG AT 1870' WITH 125 SX CMT. (FLUID LEVEL CAME UP 400') PULL TBG TO 850' & LOAD HOLE. 2ND PLUG AT 850' WITH 60 SX CMT. 3RD PLUG AT 64' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5022	5040		
4534	4539		

Remarks: USED CLASS C COMMON CEMENT BY ORR ENTERPRISES.


Plugged through: TBG

RECEIVED
APR 26 2012

KCC WICHITA

District: 01

Signed



(TECHNICIAN)

RECEIVED

APR 23 2012

KCC DODGE CITY

Form CP-2/3

5/07/12

ROOZY