

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-25375-00-00
Spot: SWNWSENV Sec/Twnshp/Rge: 9-17S-25W
1750 feet from N Section Line, 1360 feet from W Section Line
Lease Name: GIESS "E" Well #: 2
County: NESS Total Vertical Depth: 4483 feet

Operator License No.: 5123
Op Name: PICKRELL DRILLING COMPANY, INC.
Address: 100 S MAIN STE 505
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	269		WITH 160 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 04/19/2012 8:30 AM
Plug Co. License No.: 5123 Plug Co. Name: PICKRELL DRILLING COMPANY, INC.
Proposal Rcvd. from: MIKE KERNS Company: PICKRELL DRILLING COMPANY, I Phone: (316)262-8427

Proposed Plugging Method: 1ST PLUG AT 1910' WITH 50 SX CMT. 2ND PLUG AT 1170' WITH 40 SX CMT. 3RD PLUG AT 600' WITH 40 SX CMT. 4TH PLUG AT 300' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: NONE
Date/Time Plugging Completed: 04/19/2012 10:30 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

Perfs:

1ST PLUG AT 1910' WITH 50 SX CMT. 2ND PLUG AT 1170' WITH 40 SX CMT. 3RD PLUG AT 600' WITH 40 SX CMT. 4TH PLUG AT 300' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

RECEIVED
APR 26 2012

KCC WICHITA

District: 01

Signed

Michael Maier

(TECHNICIAN)

RECEIVED

APR 19 2012

KCC DODGE CITY

Form CP-2/3

5/07/12

AMZ