

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21558-00-00
Spot: SENESW Sec/Twnshp/Rge: 31-9S-17W
1650 feet from S Section Line, 2970 feet from E Section Line
Lease Name: WESTHUSIN Well #: 4
County: ROOKS Total Vertical Depth: 3615 feet

Operator License No.: 5552
Op Name: GORE OIL COMPANY
Address: 202 S ST FRANCIS PO BOX 2757
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	231		165 SX
PROD	4.5	3613		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/28/2012 9:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: LENNY DINKEL Company: GORE OIL COMPANY Phone: (316) 263-3535

Proposed
Plugging
Method:

Ordered 325 sx 60/40 pozmix - 4% gel w/500 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/28/2012 11:45 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing back in hole. Screwed into tubing at 1656'. Pumped 75 sx 60/40 pozmix 4% gel.
Unscrewed tubing at 1656'. Pumped 100 sx 60/40 pozmix 4% gel w/300 # hulls.
Pulled tubing to 800', pumped 25 sx 60/40 pozmix 4% gel w/75 # hulls to circulate to surface.
Pulled tubing out of hole. Hooked to 4 1/2" casing, pumped 75 sx 60/40 pozmix gel. Max
pressure of 500 psi. Shut in pressure at 400 psi.
Backside full of cement, pressured to 300 psi.

Perfs:

Top	Bot	Thru	Comments
3502	3507		
3488	3490		
3466	3468		
3448	3450		

Remarks: SWIFT SERVICES

Plugged through: TBG

District: 04

Signed _____

Pat Bedore

(TECHNICIAN)

RECEIVED

CM

APR 27 2012 Form CP-2/3

KCC WICHITA

APR 25 2012