

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-00250-00-01  
Spot: SENWSW Sec/Twnshp/Rge: 11-26S-7E  
1610 feet from S Section Line, 4353 feet from E Section Line  
Lease Name: MARSHALL Well #: 2  
County: BUTLER Total Vertical Depth: 2826 feet

Operator License No.: 32702  
Op Name: KUTTER OIL, INC.  
Address: 701 E RIVER ST  
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	95		75 SX
PROD	5.5	2825		150 SXS

Well Type: OIL UIC Docket No: D20116.0 Date/Time to Plug: 02/20/2012 8:00 AM  
Plug Co. License No.: 32701 Plug Co. Name: C & G DRILLING, INC.  
Proposal Rcvd. from: TIM GULICK Company: KUTTER OIL, INC. Phone: (620) 583-4306

Proposed Plugging Method: AS PER KCC RULES & REGS/ SAND @ 2710' W/5 SXS, PERF @ 250', CIRCULATE 250'-0'/ 60/44 POZMIX

Plugging Proposal Received By: DUANE KRUEGER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/22/2012 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

2/16/2012, RIH W/TBG @ 1190' TAGGED SOLID. POOH W/TBG. 2/20/2012, RIH W/BIT & TBG @ 1190', ON STEEL, BIT WAS BINDING AND DID NOT WANT TO ROTATE. CIRCULATED HOLE CLEAN. CIRCULATED OUT SCALE, GRASS, & SHALE FROM WELL. LAYED DOWN TBG & BIT. RIH W/IMPRESSION BLOCK, BLOCK CAUGHT 1-1/2" OF THREADS ON EDGE, LOOKING LIKE POSSIBLE THREAD LOOKING UP. SDON. 2-21-2012, RIH W/WASHOVER PIPE TRYING TO CIRCULATE WELL DOWN & FISH STEEL FROM WELL. DECIDED WE ARE OUTSIDE CASING. 2-22-2012, RIH W/TBG @ 1186', CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 50 SXS CLASS A COMMON 3% CC AND DISPLACED IN CASING. LAYED DOWN TBG. WAITED 2 HOURS TAGGED CEMENT @ 900'. RIH ON WIRELINE SHOT SQUEEZE HOLES 250'-251' 2 HOLES PER FT. RIH W/TBG @ 250', ESTABLISHED CIRCULATION, CONSOLIDATED MIXED & PUMPED 100 MSXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. SWEDGED INTO 5-1/2 CASING & SQUEEZED CEMENT AROUND. LAYED DOWN TBG, TOPPED WELL BACK TO SURFACE W/CEMENT. P&A COMPLETE 2:00 PM 2-22-2012.

Perfs:

Top	Bot	Thru	Comments
2768	2786	CSG	

Remarks: COMPLIANCE/ 10 YEAR RULE

Plugged through: TBG

District: 02

Signed

Duane Krueger  
(TECHNICIAN)

✓ 5/10/12

RECEIVED  
Form CP-2/3  
APR 27 2012  
KCC WICHITA

✓ JK