

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-22028-00-00
Spot: NESENW Sec/Twnshp/Rge: 20-7S-17W
1650 feet from N Section Line, 2310 feet from W Section Line
Lease Name: KRILEY F Well #: 5
County: ROOKS Total Vertical Depth: 3319 feet

Operator License No.: 5663
Op Name: HESS OIL COMPANY
Address: PO BOX 1009
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1150		425 SX
PROD	5.5	3326		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/27/2012 12:00 PM
Plug Co. License No.: 31528 Plug Co. Name: MIKE KELSO OIL, INC.
Proposal Rcvd. from: BRYAN HESS Company: HESS OIL CO. Phone: (620) 241-4640

Proposed
Plugging
Method:

Ordered 215 sx 60/40 pozmix - 4% gel w/ 500 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/27/2012 2:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Sanded back to 3230' w/5 sx 60/40 pozmix 4% gel.
Shot casing off at 1860', pumped 205 sx 60/40 pozmix 4% gel w/200 # hulls.
Pulled casing to 1200', pumped 25 sx 60/40 pozmix 4% gel.
Pulled casing to 650', pumped 100 sx 60/40 pozmix 4% gel w/200 # hulls.
Pulled casing to 200', pumped 68 sx 60/40 pozmix 4% gel w/100 # hulls to circulate to surface.
Pulled all casing. Standing full.

Perfs:

Top	Bot	Thru	Comments
3287	3292		ARBUCKLE

Remarks: COPELAND ACID AND CEMENT

Plugged through: CSG

District: 04

Signed _____

Pat Bedore

(TECHNICIAN)

5/07/12
CM

APR 25 2012

RECEIVED Form CP-2/3

APR 27 2012

KCC WICHITA