

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21565-00-00
Spot: NENESW Sec/Twnshp/Rge: 20-7S-17W
2310 feet from S Section Line, 2310 feet from W Section Line
Lease Name: KRILEY E Well #: 1
County: ROOKS Total Vertical Depth: 3288 feet

Operator License No.: 5663
Op Name: HESS OIL COMPANY
Address: PO BOX 1009
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3227		
SURF	8.625	757		325 SX
SURF	8.625	1180		
PROD	5.5	3279		
PROD	5.5	3280		600 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/29/2012 3:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: BRYAN HESS Company: HESS OIL CO Phone: (620) 241-4640

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix - 4% gel
500 # hulls

Plugging Proposal Received By: PAT BEDORE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/29/2012 5:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Perforated at 1180'.
Sanded off perforations and bail dumped 5 sx 60/40 pozmix 4% gel to 2970'.
Ran tubing to 1800' pumped 205 sx 60/40 pozmix 4% gel w/200 # hulls.
Pulled tubing to 1180', pmped 176 sx 60/40 pozmix 4% gel w/300 # hulls to circulate to surface.
Pulled all tubing. Topped off 5 1/2" casing w/19 sx 60/40 pozmix 4% gel.
8 5/8" surface pipe had cement to surface.

Perfs:

Top	Bot	Thru	Comments
3038	3165		

Remarks: COPELAND ACID AND CEMENTING

Plugged through: TBG

District: 04

Signed _____

Pat Bedore

(TECHNICIAN) RECEIVED

CM

APR 25 2012

APR 27 2012 Form CP-2/3

KCC WICHITA