

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-20530-00-01
Spot: NWNWSESW Sec/Twnshp/Rge: 23-33S-5E
1316 feet from S Section Line, 3720 feet from E Section Line
Lease Name: MILLER Well #: 3
County: COWLEY Total Vertical Depth: 3049 feet

Operator License No.: 4699
Op Name: PHILLIPS OIL PROPERTIES INC.
Address: 1822 S MEAD
WICHITA, KS 67211

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	200		120 SX
PC		1681		181 SX CMT
PROD	5.5	3049		100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/23/2012 8:00 AM
Plug Co. License No.: 31539 Plug Co. Name: SAMS WELL SERVICE, INC.
Proposal Rcvd. from: TROY PHILLIPS Company: PHILLIPS OIL PROPERTIES Phone: (316) 265-7779

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 04/24/2012 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/ TBG @ 2800', CONSOLIDATED OIL WELL SERVICES PUMPED 38 SXS SAND, LET SAND FALL 30 MIN. W/ TBG @ 2800', CONSOLIDATED MIXED & PUMPED 25 SXS 60/40 POZMIX 4% GEL 2% CC AND DISPLACED IN CASING. WAITED 2 HRS. TAGGED CEMENT @ 2608'. SDON . 4-24-2012, RIH W/TBG @ 1653', CONSOLIDATED MIXED & PUMPED 50 SXS 60/40 POZMIX 4% GEL 2% CC & DISPLACED IN CASING. WAITED 2 HOURS, TAGGED CEMENT @ 1520'. RIH W/TBG @ 275', CONSOLIDATED OILWELL SERVICES MIXED & PUMPED 47 SXS 60/40 POZMIX 4% GEL 2% CC TO SURFACE. CEMENT CIRCULATED. CONSOLIDATED OILWELL CEMENT TICKET #34322.

Perfs:

Top	Bot	Thru	Comments
3014	3022	CSG	
2954	2960	CSG	

Remarks:

Plugged through: TBG

District: 02

Signed


(TECHNICIAN)

RECEIVED

Form CP-2/3

APR 27 2012

KCC WICHITA