

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-22895-00-00
Spot: NESWNESW Sec/Twnshp/Rge: 32-33S-6E
1965 feet from S Section Line, 3556 feet from E Section Line
Lease Name: BERRY Well #: 9
County: COWLEY Total Vertical Depth: 3100 feet

Operator License No.: 34470
Op Name: VICTORY MINERALS LLC
Address: PO BOX 414931
KANSAS CITY, MO 64141

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	200		100 SX
PROD	4.5	3100		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/18/2012 8:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: CARMON DECKER Company: VICTORY MINERALS LLC Phone: (816) 223-3712

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 02/27/2012 12:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE SHOT SQUEEZE HOLES @ 350'-351'. 2-27-2012, RIH W/TBG @ 319', SETTING DOWN SOLID ON SOMETHING, CASING PARTED @ 320', OUTSIDE CASING. CIRCULATED HOLE CLEAN @ 319'. RIH WITH TBG @ 314', GRESSEL OILFIELD SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 180 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED INSIDE & ON BACKSIDE OF 4-1/2" CASING. PLUG DOWN 12:00 PM 2-27-2012. GRESSEL OILFIELD CEMENT TICKET #38016. 2-28-2012, TAGGED CEMENT @ 75', TOPPED WELL BACK TO SURFACE W/12 SXS CLASS A COMMON, P & A COMPLETE.

Perfs:

Remarks: COMPLIANCE /10 YR RULE

Plugged through: TBG

District: 02

Signed

Duane Krueger
(TECHNICIAN)

5/14/12
RECEIVED Form CP-2/3
APR 27 2012
KCC WICHITA