

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-19664-00-00
Spot: E2SWNWSW Sec/Twnshp/Rge: 31-25S-5E
1669 feet from S Section Line, 4927 feet from E Section Line
Lease Name: ROBINSON A Well #: 58
County: BUTLER Total Vertical Depth: 2468 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	79		65 SX
PROD	5.5	2440		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/11/2012 8:00 AM
Plug Co. License No.: 32991 Plug Co. Name: SIMMONS WELL SERVICE, INC.
Proposal Rcvd. from: CASEY COATS Company: VESS OIL CORPORATION Phone: (316) 655-1997

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: NONE
Date/Time Plugging Completed: 04/11/2012 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 2380', CONSOLIDATED WELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 50 SXS 60/40 POZMIX 4% GEL, 3% CC & DISPLACED IN CASING. WAITED 2 HOURS, TAGGED CEMENT @ 2021'. RIH W/TBG @ 1690', CONSOLIDATED WELL SERVICES MIXED & PUMPED 75 SXS 60/40 POZMIX 4% GEL, 3% CC AND DISPLACED IN CASING, WAITED 2 HOURS, TAGGED CEMENT @ 1238'. RIH W/TBG @ 907', CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 50 SXS 60/40 POZMIX 4% GEL, 3% CC AND DISPLACED IN CASING. WAITED 2 HOURS, TAGGED CEMENT @ 692'. RIH W/TBG @ 315', CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 45 SXS 60/40 POZMIX 4% GEL, 3% CC TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 5:00 P.M., 4-11-2012. CONSOLIDATED OIL WELL SERVICES TICKET #34310.

Perfs:


Top	Bot	Thru	Comments
2440	2468	OH	
2013	2081	CSG	
1722	1778	CSG	

Remarks:

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

RECEIVED Form CP-2/3

APR 27 2012

KCC WICHITA

5/14/12

✓