

TO:  
STATE CORPORATION COMMISSIO  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 6720

API Well Number: 15-049-22564-00-00  
Spot: NENESENW Sec/Twnshp/Rge: 12-30S-12E  
3645 feet from S Section Line, 2806 feet from E Section Line  
Lease Name: CODY Well #: 7  
County: ELK Total Vertical Depth: 1089 feet

Operator License No.: 7786

Op Name: CODY, KEN L.

Address: 1125 RD 27  
LONGTON, KS 67352

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	43		16 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 03/27/2012 12:00 AM

Plug Co. License No.: 32884

Plug Co. Name: ELMORE'S, INC.

Proposal Rcvd. from: KEN L. CODY

Company:

Phone: (620) 642-6123

Proposed  
Plugging  
Method:

Cementing to be done through 2 3/8" tubing. Gel hole at 1089'. Spot 12 sacks of cement at 1089'. Pull up to 750' and spot  
'12 sacks of cement: Pull up to 350' and cement to surface .

Plugging Proposal Received By: DUANE SIMS

WitnessType: NONE

Date/Time Plugging Completed 03/27/2012 10:00 AM

KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Ran 1" to 1080' gelled hole and spotted 10 sack plug. Pulled up to 750' and spotted 10 sack  
plug. Pulled up to 350' and circulated cement to surface. Pulled 1" and topped well off. A total  
of 130 sacks of cement were used to plug this well.

RECEIVED

APR 18 2012 DAS


KCC Chanute Dist. #3

Remarks:

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)

RECEIVED

Form CP-2/3

APR 30 2012

KCC WICHITA