


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Ness County. Sec. 13 Twp. 16 S Rge. 22 W (E) (W)
Location as "NE/CNW&SW¼" or footage from lines C SE NW
Lease Owner M & O Oil Company, Inc.
Lease Name Sunley Well No. #1
Office Address P. O. Box #791 Fort Scott, Kansas 64112
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed February 23 19 68
Application for plugging filed February 23 19 68
Application for plugging approved February 23 19 68
Plugging commenced February 23 19 68
Plugging completed February 23 19 68
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey -, Box #582 - Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4391 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	240'	8 5/8"	240'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug:

660'/70 sacks cement
200'/20 sacks cement
40'/10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION
MAR 11 1968
CONSERVATION DIVISION
Wichita, Kansas

03-11-1968

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor HELLAR DRILLING COMPANY, INC.
Address 1014 Union Center, Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.
D. L. Hellar, President of Hellar Drilling Co (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) D. L. Hellar D. L. Hellar, President
1014 Union Center Bldg., Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN to before me this 8th day of March, 1968

My commission expires October 5, 1968

Mildred Saxton
Mildred Saxton Notary Public.

DRILLERS' LOG

COMPANY: M & O Oil Company, Inc.- Box 791-Fort Scott, Kansas
 CONTRACTOR: Hellar Drilling Company, Inc- Wichita, Kansas
 LEASE: Sunley #1
 LOCATION: C SE NW Section 13-16S-22W, Ness County, Kansas
 COMMENCED: February 14, 1968
 COMPLETED: February 23, 1968
 CASING: Set 8 5/8" Surface Casing @ 240'/175 Sacks Cement

0-240	Sand and clay
240-435	Shale
435-1055	Shale and shells
1055-1160	Red Beds
1160-1375	Sand
1375-1714	Shale and shells
1714-1752	Anhydrite
1752-2170	Shale and red beds
2170-2415	Salt section
2415-2575	Ft. Riley - Chert and Limestone
2575-3790	Limestone and shale
3790-4265	Limestone and shale streaks
4265-4335	Limestone and shale
4335-4383	Shale and sand
4383-4391	Limestone and chert
4391	Rotary Total Depth

RECEIVED
 STATE CORPORATION COMMISSION
 MAR 11 1968
 CONSERVATION DIVISION
 Wichita, Kansas
 03-11-1968

D & A

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, D. L. Hellar, do hereby certify that the above and foregoing is a true and correct copy of the log of the #1 Sunley, located in C SE NW Section 13-16S-22W, Ness County, Kansas, as reflected by the files of the Hellar Drilling Company, Inc.

HELLAR DRILLING COMPANY, INC.

BY *D. L. Hellar*
 .PRESIDENT - D. L. Hellar

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 8th day of March, 1968.

MY COMMISSION EXPIRES:
October 5, 1968

Mildred Saxton
 Notary Public - Mildred Saxton