

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-135-23,563-00-00

LEASE NAME Richardson

WELL NUMBER #1 D

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 12 TWP. 16S RGE. 22W (for W)

COUNTY Ness

Date Well Completed

Plugging Commenced 5-31-91

Plugging Completed 6-5-91

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Bankoff Oil Company

ADDRESS P.O. Box 1374 Great Bend, KS. 67530

PHONE (316) 793-2061 OPERATORS LICENSE NO. 6040

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)
 by (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4378'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED
 STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	270'	none
				5 1/2"	4377'	3362'

JUN 12 1991
 OIL DIVISION
 WICHITA, KANSAS

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Sanded bottom to 4230' ran 5 sacks cement. Shot pipe @3538', 3362'
Pulled up to 1580' spotted 50 sacks, pulled to 1000' spotted
80 sacks, pulled to 300' spotted 40 sacks, pulled to 40' 10 sacks
60/40 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Bankoff Oil Company

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of
 above-described well, being first duly sworn on oath, says: That I have knowledge of the facts,
 statements, and matters herein contained and the log of the above-described well as filed that
 the same are true and correct, so help me God.

(Signature) *R. Darrell Kelso*

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 10 day of June, 19 91

Irene Herzberg
 Notary Public

My Commission Expires:



15-135-23563-00-00

ELDON'S COPY MARKED



WIRE-TECH

COMPENSATED DENSITY NEUTRON LOG

COMPANY <u>BANKOFF OIL COMPANY</u>		RECEIVED STATE CORPORATION COMMISSION
WELL <u>#1 D RICHARDSON</u>		APR 15 1991
FIELD _____		04-15-1991 CONSERVATION DIVISION Wichita, Kansas
COUNTY <u>NESS</u>	STATE <u>KANSAS</u>	
Location <u>SW NE SE</u>		Other Services: DIL
Sec. <u>12</u>	Twp. <u>16S</u>	Rge. <u>22W</u>

Permanent Datum <u>GROUND LEVEL</u>	Elev. <u>2369'</u>	Elev.: K.B. <u>2378'</u>
Log Measured From <u>K.B.</u>	<u>11</u> Ft. Above Perm. Datum	D.F. _____
Drilling Measured From <u>KELLY BUSHING</u>		G.L. <u>2369'</u>

Date	3-27-91		
Run No.	ONE		
Depth—Driller	4376'		
Depth—Wire Tech	4379'		
Bl. Log Inter.	4378'		
Top Log Inter.	3600'		
Casing—Driller	8 5/8" @ 270'	170 sx cem	
Casing—Wire Tech	5 1/2 4377	100 sx cem	
Bit Size	7 7/8"		
Type Fluid in Hole	CHEMICAL MUD		
CHLORIDES	5500 PPM		
Dens. Visc.	9.3 61		
pH Fluid Loss	9 9.8 ml		
Source of Sample	FLOWLINE		
R _m @ Meas. Temp.	1. @ 70 °F	.62 @ 117 °F	
R _{ml} @ Meas. Temp.	.72 @ 70 °F	.44 @ 117 °F	
R _{mc} @ Meas. Temp.	1.4 @ 70 °F	.86 @ 117 °F	
Source R _{ml} R _{mc}	CHARIS I		
R _m @ BHT	1. @ 117 °F		
Time Since Circ.	5 HOURS		
Max. Rec. Temp.	117°F @ T.D.		
Equip. Location	60 GREAT BEND, KANSAS		
Recorded By	W. CURTIS		
Witnessed By	F. MIZE J. ZORGER		

WT 2

Top cem 3700 (NO PB)