


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Ness County, Sec. 8 Twp. 16S Rge. 22W ~~QEX~~ KXX
Location as "NE/CNWSW" or footage from lines SW NE NW
Lease Owner The National Oil Company
Lease Name Hogsett Well No. 1
Office Address Suite 550, O.W. Garvey Bldg., Wichita, Ks. 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed March 11, 1974
Application for plugging filed Verbal Application 19 74
Application for plugging approved Verbal Approval 19 74
Plugging commenced March 11, 1974
Plugging completed March 11, 1974
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19 _____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4,630 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	219'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 4,630 feet (rotary total depth) to 720 feet. Set plug at 720 feet and cemented with 70 sacks cement. Filled hole with heavy rotary mud from 720 feet to 210 Feet. Set plug at 210 feet and cemented with 20 sacks cement. Filled hole with heavy rotary mud from 210 feet to 40 feet. Set solid plug at 40 feet and cemented to cellar with 10 sacks cement, two sacks cement in rat hole.

Plugging operations accomplished utilizing Halliburton Oil Well Cementing pump truck through 4 1/2 inch drill pipe.

RECEIVED
STATE CORPORATION COMMISSION

MAR 18 1974
03-18-1974

Name of Plugging Contractor H-30, Inc. (If additional description is necessary, use BACK of this sheet)
Address 200 North Main, Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Dean Britting, Agent (~~XXXXXX~~ of owner) (~~XXXXXX~~) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Britting
200 No. Main, Wichita, Kansas 67202
(Address)

Subscribed and sworn to before me this 15th day of March, 19 74

My commission expires June 30, 1974

Elsie Willison
Notary Public.



KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **The National Oil Company**

15-135-20840-00-00
 SEC. 8 T. 16S R. 22W
 LOC. SW NE NW

FARM **Hogsett**

NO. **1**

COUNTY **Ness**

TOTAL DEPTH **4,630'**


COMM. **February 27, 1974**

COMP. **March 11, 1974**

SHOT OR TREATED

CONTRACTOR **H-30, Inc.**

ISSUED



CASING

20	10	
15	8	-5/8" 219' cemented w/155 sxs cement
12	6	
13	5	

LEVATION **2,360' KB**

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Post Rock, Shale and Sand	221'
Shale and Red Bed	1,150'
Sandstone	1,410'
Shale	1,705'
Anhydrite	1,735'
Red Bed and Shale	2,050'
Shale and Shells	2,425'
Shale, Shells and Lime	2,704'
Shale and Lime	2,798'
Lime and Shale	2,860'
Shale and Lime	3,138'
Lime	3,225'
Shale and Lime	3,473'
Lime	4,306'
Lime and Chert	4,422'
Lime	4,544'
Lime and Chert	4,596'
Lime	4,630'
Rotary Total Depth	4,630'

RECEIVED
 STATE CORPORATION COMMISSION
 MAR 19 1974
 CONSERVATION DIVISION
 Wichita, Kansas
 03-18-1974

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Dean Britting
 Dean Britting

State of Kansas

County of Sedgwick

} ss:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 15th. day of March, 1974.

Elsie Willison
 Elsie Willison -Notary Public

My Commission Expires:

June 30, 1974

