

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-135-24219-0000

LEASE NAME Virginia

WELL NUMBER 1

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

2,260' Ft. from N Section Line

1,910' Ft. from E Section Line

SEC. 8 TWP. 16 RGE. 22 (X) or (W)

COUNTY Ness

LEASE OPERATOR Coral Coast Petroleum, LC

ADDRESS 200 East First, STE #001, Wichita, KS

PHONE#(316) 269-1233 OPERATORS LICENSE NO. 31,691

Date Well Completed 4-13-03

Character of Well D & A

RECEIVED  
04-18-2003  
APR 18 2003  
KGG WICHITA  
Logging Commenced 4-13-03

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

Logging Completed 4-13-03

The plugging proposal was approved on 4-13-03 (date)

by Steve Pfeifer (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4,446'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	227'	Cmtd. w/160 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each as follows: Push bridge plug to 1,804', pump 50 sax cement down drill pipe; push bridge plug to 1,050', pump 80 sax cement down drill pipe; push bridge plug to 500', pump 40 sax cement down drill pipe; push wiper plug to 40', dump 10 sax cement on plug to cellar; dump 15 sax cement down rat hole and 10 sax cement down mouse hole.

Name of Plugging Contractor Shields Drilling Co. License No. 5184

Address Shields Bldg., PO Box 709, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Coral Coast Petroleum, LC

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman, Sec.-Treas

Contractor

(Employee of ~~XXXXXX~~) or (~~XXXXXX~~)  
above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed in the same are true and correct, so help me God.

(Signature) Jack P. Beeman

(Address) PO Box 709, Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 16th day of April, 2003

[Signature]  
Notary Public

My Commission Expires: \_\_\_\_\_

Notary Public  
State of Kansas  
Exp. 5/2/03