


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Ness County, Sec 4 Twp 16S Rge. (E) 22(W)  
Location as "NE/CNW/SW" or footage from lines Approx. C SE NW  
Lease Owner John C. Graves, et al  
Lease Name Wyman Well No. 1  
Office Address 505 Union Center, Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed September 11, 19 68  
Application for plugging filed September 11, 19 68  
Application for plugging approved September 11, 19 68  
Plugging commenced September 11, 19 68  
Plugging completed September 11, 19 68  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays, Kansas  
Producing formation Depth to top Bottom Total Depth of Well 4425 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	228'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up with heavy mud to 720 feet. Followed by wooden plug and 1/2 sack hulls. Placed 70 sacks cement onto hulls. Mudded up with heavy mud to 210 feet followed by wooden plug, 1/2 sack hulls and 20 sacks cement. Mudded up with heavy mud to 40 feet followed by wooden plug, 1/2 sack hulls and 10 sacks cement to base of well cellar. Plugged rat hole with 2 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 1 - 1968  
CONSERVATION DIVISION  
Wichita, Kansas  
10-01-1968

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Graves Drilling Co., Inc.  
Address 505 Union Center, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
John C. Graves (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John C. Graves  
505 Union Center, Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of September, 19 68  
Betty Brandt  
Notary Public.

My commission expires May 9, 1971

15-135-20183-00-00

R O T A R Y D R I L L E R S ' L O G

OPERATOR: John C. Graves, et al DRILLING COMMENCED: September 5, 1968  
 505 Union Center  
 Wichita, Kansas 67202

CONTRACTOR: Graves Drilling Co., Inc. DRILLING COMPLETED: September 11, 1968  
 505 Union Center  
 Wichita, Kansas 67202

CASING RECORD: 11 Jts. 228' 8-5/8" LOCATION: Wyman No. 1  
 cemented with 150 sacks Approx. C SE NW  
 Section 4-16S-22W  
 Ness County, Kansas

-----

0 - 229	Sand	3400 - 3501	Lime & shale
229 - 429	Shale	3501 - 3783	Lime
429 - 700	Shale & shells	3783 - 3805	Shale & lime
700 - 1501	Sand & shale	3805 - 3818	Lime & shale
1501 - 1750	Shale & shells	3818 - 4085	Lime
1750 - 1791	Anhydrite	4085 - 4167	Shale & lime
1791 - 2100	Shale & shells	4167 - 4259	Lime
2100 - 2600	Shale & lime	4259 - 4272	Shale
2600 - 2780	Lime & shale	4272 - 4370	Lime & shale
2780 - 3145	Lime	4370 - 4373	Lime
3145 - 3268	Lime & shale	4373 - 4376	Shale & sand
3268 - 3330	Shale	4376 - 4425	Chert
3330 - 3400	Lime	4425	Rotary Total Depth

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC. RECEIVED  
 STATE CORPORATION COMMISSION  
 OCT 1 - 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas  
 By John C. Graves President

10-01-1968

STATE OF KANSAS )  
 ) ss:  
 SEDGWICK COUNTY )

Subscribed and sworn to before, a Notary Public, this 17th of September, 1968.

Betty Brandt  
 Betty Brandt Notary Public

My commission expires:  
 May 9, 1971