

LEASE NAME Elmore

WELL NUMBER 1

4950 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 29 TWP. 17S RGE. 25 (X or W)

COUNTY Ness

Date Well Completed 8/29/95

Plugging Commenced 5:30AM 8/29/95

Plugging Completed 8:00AM 8/29/95

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Benson-McCown & Co.

ADDRESS 1616 S. Kentucky C-305 Amarillo, TX 79102

PHONE (806) 353-7429 OPERATORS LICENSE NO. 09220

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8/28/95 (date)

by Richard Lacey (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.O. 4475'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		Surface	206	8 5/8	206 90	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set

1st plug @ 1830' w/50sks 10sks in mouse hole Circulated 1st plug 15 minutes w/ 51 Vis. Mud

2nd plug @ 1060' w/80sks 15sks in rat hole Plugs displaced with mud

3rd plug @ 500' w/40sks

4th plug @ 239' w/40sks Total 245 sks 60/40 Poz 6%Gel w/1# ES/SK

5th plug @ 40' w/10sks Job Completed @ 8:00 AM-8/29/95 By Halliburton Cementing

Name of Plugging Contractor Discovery Drilling License No. 31548

Address P.O. Box 763 Hays, Kansas 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Benson McCown & Co.

STATE OF TEXAS COUNTY OF POTTER, ss.


CARL H. BENSON (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) Carl H. Benson

(Address) 1616 S. Kentucky Bldg C-305

AND SWORN TO before me this 11th day of September, 19 95

Paula A. Breeding
 Notary Public



My Commission Expires: 12-9-97
USE ONLY ONE SIDE OF EACH FORM