

15-135-20699-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

Ness County. Sec. 29 Twp. 17S Rge. 25 (W)
C NW SW
Location as "NE/CNW/SW" or footage from lines
Lease Owner Pickrell Drilling Company
Lease Name Norton-Reed "A" Well No. 1
Office Address 705 Fourth National Bank Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 22 19 72
Application for plugging filed October 22 19 72
Application for plugging approved October 22 19 72
Plugging commenced October 22 19 72
Plugging completed October 22 19 72
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4468 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	258'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bottom Plug @ 725' w/88 sacks, Middle Plug @ 270' w/30 sacks,
Top Plug @ 40' w/10 sacks.

RECEIVED
STATE CORPORATION COMMISSION
OCT 30 1972
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Pickrell Drilling Company
Address 705 Fourth National Bank Building, Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick ss.
C. W. Sebitts (employee of owner) or (owner or operator) of the above-described

well, do hereby, first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebitts
705 Fourth National Bank Bldg., Wichita, Kansas
(Address)

Subscribed and sworn to before me this 26th day of October, 19 72

Esther Lamone
Notary Public.

My commission expires January 19, 1973



ROTARY DRILLING LOG 15-135-20699-0000

COMPANY: Pickrell Drilling Company
705 Fourth National Bank Building
Wichita, Kansas 67202

Rotary Drilling Commenced 10/11/72

Rotary Drilling Completed 10/22/72

LOCATION: Norton-Reed "A" No. 1, C NW SW Sec. 29-17S-25W,
Ness County, Kansas

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: Run 6 Jts. 8-5/8" surface casing set @ 258'. Cemented w/140
sacks 3/2 cement. Completed 6:15 P.M. Circulated.

No oil string run. D & A, Plugged 5:00 P.M. October 22, 1972.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

60	Post Rock	<u>C.F.S.</u>
260	Shale & Shells	4225
840	Shale & Sand Streaks	4245
1000	Shale - Sand	4360
1195	Red Beds	4430
1225	Blain	4440
1380	Red Beds - Shale	4445
1530	Sand	4455
1795	Red Beds & Shale	4465
1840	Anhydrite	4468
2060	Shale	
2300	Shale & Lime	
3595	Lime	
3760	Shale & Lime	
4305	Lime	
4360	Lime & Shale	
4425	Lime	
4468	Mississippian, RTD	

Slope Tests

2000
2500
3000
3500
4000

RECEIVED
STATE CORPORATION COMMISSION
OCT 30 1972
CONSERVATION DIVISION
Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS

COUNTY OF SEDGWICK } ss.:

On this 26th day of October, 19 72, before me the undersigned, a Notary Public, in and for

the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: January 19, 1973

Esther Lamore
C. W. Sebitts Notary Public