

15-135-20421-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

NESS County, Sec. 27 Twp. 17 Rge. 25 ## (W)

Location as "NE/CNW/SW" or footage from lines N/2 NE NE

Lease Owner Palomino Petroleum

Lease Name Shearer Well No. 1

Office Address 304 Insurance Bldg. Wichita, Kansas 67202

Character of Well (completed as Oil, Gas or Dry Hole) oil

Date well completed March 16 1971

Application for plugging filed August 17 1972

Application for plugging approved August 18 1972


Plugging commenced 8 / 17 1972

Plugging completed 8 / 29 1972

Reason for abandonment of well or producing formation non-commercial

If a producing well is abandoned, date of last production August 10 1972

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Leo Massey

Producing formation Mississippian Depth to top 4437 Bottom 4489 Total Depth of Well 4489 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	240'	0
				5 1/2	4418	1496'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with sand from 4418' to 4400' run 5 sacks of cement from 4400' to 4370'

Had 3 sacks of hulls 20 sacks of gel mud 70 sacks of cement, 10 gel mud a plug and 50 sacks of cement pumped in 8 5/8" pipe to plug well.

RECEIVED
STATE CORPORATION COMMISSION

SEP 11 1972
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Glenn & Smith Pipe Pulling Co.

Address Box 156 Ellinwood, Kansas 67526

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

R. W. Watchous (employee or owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

304 Insurance Bldg., Wichita, Ks. 67202


(Address)

Subscribed and Sworn to before me this 8th day of September, 1972

My commission expires October 8, 1972

Celia A. Smith
Celia A. Smith

Notary Public.



DRILLER'S LOG

COMPANY: Palomino Petroleum, 304 Insurance Bldg., Wichita, Kansas 67202
 CONTRACTOR: Hellar Drilling Company, Inc., Wichita, Kansas 67202
 LEASE: #1 Shearer
 LOCATION: N/2 NE/4 NE/4 27-17S-25W, Ness County, Kansas
 COMMENCED: March 5, 1971
 COMPLETED: March 16, 1971
 CASING: Set 8 5/8" Surface Casing @ 240'/175 sacks cement
 Set 5 1/2" Casing @ 4438'/100 sacks cement

0-70	Rock
70-240	Shale&Sand
240-835	Shale - Red Bed
835-1758	Shale
1758-1788	Anhydrite
1788-1875	Shale
1875-2170	Salt Section
2170-2595	Shale & Lime
2595-3865	Lime (L.K.C.)
3865-4446	Lime
4446-	Rotary Total Depth

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 18 1972
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, D. L. Hellar, do hereby certify that the above and foregoing is a true and correct copy of the log of the #1 Shearer, located in N/2 NE/4 NE/4 27-17S-25W, Ness County, Kansas as reflected by the files of the Hellar Drilling Company, Inc.

HELLAR DRILLING COMPANY, INC.

By *D. L. Hellar*
 President - D. L. Hellar

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 23rd day of March, 1971.



Catherine Darcey
 Notary Public - Catherine Darcey

My Commission Expires:

March 25, 1972.