

15-135-21513-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Ness County, Sec. 25 Twp. 17S Rge. 25 XE/W
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines
E/2 NE NE

Lease Owner Petroleum, Inc.
Lease Name Schaben Well No. 1
Office Address 800 R.H. Garvey Bldg., Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole) dry hole



Locate well correctly on above
Section Plot

Date Well completed 9-13 19 78
Application for plugging filed 9-13 19 78
Application for plugging approved 9-13 19 78
Plugging commenced 9-13 19 78
Plugging completed 9-13 19 78

Reason for abandonment of well or producing formation
no commercial quantities of oil or gas encountered

If a producing well is abandoned, date of last production
-- 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4450
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface hole	shale	surf	286'	8-5/8"	286'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Fluid to 700', plug, 70 sx
Fluid to 240', plug, 20 sx
Fluid to 40', plug, 10 sx

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor D N B DRILLING, INC.
515 R. H. Garvey Building
Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.
Ella Priess (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ella Priess
Suite 515 R.H. Garvey Bldg., Wichita, Ks.
(Address) 67202

SUBSCRIBED AND SWORN TO before me this 14th day of September, 19 78

Dorothy L. Schmidt
Dorothy L. Schmidt Notary Public.

My commission expires April 30, 1979

RECEIVED
STATE CORPORATION COMMISSION

SEP 19 1978

CONSERVATION DIVISION
Wichita, Kansas

DOROTHY L. SCHMIDT
STATE NOTARY PUBLIC
Sedgwick County, Kansas
My Appt. Exp. April 30, 1979

RECEIVED
STATE CORPORATE COMMISSION

SEP 19 1978

CONSERVATION DIVISION
Wichita, Kansas

DRILLER'S LOG

PETROLEUM, INC.
No. 1 Schaben
E/2 NE NE Sec. 25-17S-25W
Ness Co., Ks.

Commenced: 9-5-78
Completed: 9-13-78

Surface Casing: 278' of 8-5/8"
cemented w/175 ex common, 2% gel,
3% cc. 9-5-78

FORMATION

DEPTH

Surface Hole	0 - 286
Sand & Shale	286 - 530
Shale	530 - 1085
Blaine	1085 - 1095
Sand & Shale	1095 - 1480
Shale & Red Bed	1480 - 1711
Andydrate	1711 - 1745
Shale	1745 - 2135
Shale & Lime	2135 - 2490
Lime & Shale	2490 - 4105
Lime	4105 - 4450 RTD

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

Ella Priess

Ella Priess

STATE OF KANSAS: ss:

Subscribed and sworn to before me this 14th day of September, 1978.

Dorothy L. Schmidt
Dorothy L. Schmidt, Notary Public

DOROTHY L. SCHMIDT
STATE NOTARY PUBLIC
Sedgwick County, Kansas
My Appt. Exp. April 30, 1979