


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Ness County. Sec. 24 Twp. 17S Rge. 25W E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
C NE SE

Lease Owner John Jay Darrah, Jr.
Lease Name Schaben Well No. #1
Office Address Century Plaza Bldg. Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above
Section Plot

Date Well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 9-2-81 19
Plugging completed 9-4-81 19
Reason for abandonment of well or producing formation

Depleted
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt
Producing formation Depth to top Bottom Total Depth of Well 4390'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	298'	none
				5-1/2"	4388'	1503'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

Moved in on location, got 5" stretch. Ran sand to 4300' and set 5 sacks cement.
Shot Pipe @2988', 2542', 2016', 1727' and 1510'. Pulled 43 joints of pipe.
Plugged well with 20 sacks gel, 5 sacks hulls, 8-5/8" plug, 140 sacks 50/50 pos,
4% gel, 3% cc. Plugging completed.

RECEIVED
SEP 17 1981
STATE CORPORATION COMMISSION


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
R. Darrell Kelso
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of September, 1981



My commission expires

Irene Hoover
Notary Public.

15-135-21664-00-00

D R I L L E R S L O G

#1 Schaben

CASING RECORD:
7 jts. new 20#
8-5/8" surface
casing

COMPANY: John Jay Darrah, Jr.
CONTRACTOR: Strata Drilling Company
COMMENCED: July 24, 1979
COMPLETED: August 5, 1979

DESCRIPTION C NE SE
Section 24-17S-25W
Ness County, Kansas
ELEVATION: 2387' RKB

TOTAL ROTARY
DEPTH: 4390'

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Post rock and shale	0	310	Ran 293' new 20# 8-5/8" surface casing; set and cemented at 298' with 190 sacks common cement, 2% gel, 3% C.C. Cement circulated. Plug down at 9:30 p.m., July 24, 1979.
Shale and sand	310	1380	
Shale	1380	1644	
Anhydrite	1644	1671	
Shale	1671	2420	
Lime and shale	2420	3925	
Lime	3925	4100	
Lime and shale	4100	4390	Ran one drill stem test. Ran one electric log. Ran 130 jts. new 20# casing at 4388' with 140 sacks cement, 10% salt. Plug down at 4:30 p.m., August 5, 1979.

RECEIVED
STATE COMMISSION
AUG 24 1979
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
)ss
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING COMPANY

Charles W. Steincamp
Charles W. Steincamp

Sworn to and subscribed before me this 14th day of August, 1979.

My appointment expires 3-28-80.

Loneita Barry
Loneita Barry, Notary Public

