


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Ness County. Sec. 30 Twp. 17S Rge. 25W-E/W  
Location as "NE/CNW 1/4 SW 1/4" or footage from lines  
C-S/2 SW NE  
Lease Owner Kansas Oil Corporation  
Lease Name KU Endowment Well No. 1  
Office Address 555 N. Woodlawn, Wichita, Kansas 67208  
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole  
Date Well completed December 22, 19 80  
Application for plugging filed Verbal Application 19 80  
Application for plugging approved Verbal Approval 19 80  
Plugging commenced December 22, 19 80  
Plugging completed December 22, 19 80  
Reason for abandonment of well or producing formation \_\_\_\_\_



Locate well correctly on above  
Section Plot

If a producing well is abandoned, date of last production 19 \_\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4,474'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	269'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy rotary mud from 4,474 ft. (rotary total depth) to 1,040 ft. Set plug at 1,040 ft. and cemented with 70 sacks cement. Filled hole with heavy rotary mud from 1,040 ft. to 270 ft. Set plug at 270 ft. and cemented with 30 sacks cement. Filled hole with heavy rotary mud from 270 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 10 sacks cement, 5 sacks cement in rat hole.

Plugging operations accomplished utilizing Halliburton Services Oil Well cementing pump truck through 4 1/2 inch drill pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Services  
410 Union Center Bldg., Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.  
Gary Younger, Agent ~~Conservator~~ of owner ~~XXXXXXXXXXXXXXXXXXXX~~

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
251 N. Water - Suite 10 Wichita, KS 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of January, 1981

Elsie Willison  
Elsie Willison - Notary Public.

My commission expires July 25, 1982

JAN 23 1981

CONSERVATION DIVISION  
Wichita, Kansas

