

15-135-20791-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
SEP 17 1973
CONSERVATION DIVISION
WICHITA, KANSAS

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name D N B Drilling, Inc.
Complete Address 701 First National Bank Bldg., Wichita, Kansas
Lease Name Stieber Well No. 1
Location C SW SE Sec. 19 Twp. 17 Rge. (E) (W) 21
County Ness Total Depth 4330'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Co. Tools
Address License No.
Operation Completed: Hour 4 P Day 15 Month 9 Year 1973

The above well was plugged as follows:

RTD 4330' 8 5/8 csg set at 296' cwc Cmt. Mat. 50-50 poz W/6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 500' and displaced 50 sk
cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 25 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Luc Z. Massey
Well Plugging Supervisor

DATE 9-17-73

INV. NO. 7917-10