

15-135-20164-00-00

KANSAS

Form CP-3  
Rev. 6-26-62

R

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 15 1968  
CONSERVATION DIVISION  
Wichita, Kansas

07-15-1968

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Imperial Oil Company

Complete Address: 780 Fourth Nat'l Bldg. Wichita, Kansas

Lease Name Ramsey Well No. 1

Location C SE NE Sec. 16 Twp. 17 Rge. 21 (E) (W) X

County Ness Total Depth 4265

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Co Tools

Address:      License No.     

Operation Completed: Hour 2 P Day 11 Month 7 Year 1968

The Above well was plugged as follows:

RTD 2465' 8 5/8 csg set at 276' cwc Cem. Mat. 100 sc 50-50 poz cem. W/6% total gel.  
Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 70 sc cem.  
thru drill pipe. Heavy mud to 275' set cementing plug and displaced 20 sc cement thru  
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base  
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massey  
Well Plugging Supervisor

DATE 7-15-68  
INV. NO. 8118-W