

15-135-20002-00-00

KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

AUG 21 1967
08-21-1967
CONSERVATION DIVISION

Operator's Full Name Pickrell Drilling Company

Complete Address: 705 4th Nat'l Bk. Bldg., Wichita, Kansas

Lease Name Conner "B" Well No. 1

Location C SW SW Sec. 14 Twp. 17 Rge. 21 (E) (W) X

County Ness Total Depth 4149

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling

Address: Great Bend, Kansas License No. 49

Operation Completed: Hour 4: P Day 18 Month 8 Year 1967

The Above well was plugged as follows:

Total Depth 4149 8 5/8 csg set at 261' cwc 160 sc.

5 1/2 csg set at 4146' cw 100 sc cement.

Perf. 4136-40

Filled with sand to 4100' and dumped 5 sc cement with dump bailer.

Recov. 2610' of 5 1/2 csg.

Squeezed 8 5/8 csg with 30 sc gel and 135 sc poz cement with 6% gel.

Mud to 680' cement (200-680) mud 50-200 cement (0-50)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo. J. Massey
Well Plugging Supervisor

DATE 8-21-67

INV. NO. 6166-W