

15-135-20178-00-00

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 28 1968
CONSERVATION DIVISION
Wichita, Kansas
10-28-1968

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Pickrell Drilling Company

Complete Address: 705 4th Nat'l Bank Bldg., Wichita, Kansas

Lease Name Ryan Estate Well No. 1

Location C SW NW Sec. 23 Twp. 17 Rge. 21 (E) (W) X

County Ness Total Depth 4211

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Russ Casing Pulling

Address: Box 1082 Great Bend, Kansas License No. 62B

Operation Completed: Hour 1P Day 25 Month 10 Year 1968

The Above well was plugged as follows:

Total depth 4211' 8 5/8 csg set at 248' cwc 185 sc.

5 1/2 csg set at 4207' cw 100 sc cmt.

5 1/2 csg PBTD 4181' with top perf at 4096'.

Filled 5 1/2 csg with sand (4080-4181) Dumped 5 sc cmt with dump bailer (4080-4040)

Cutoff and recov. 3200' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 20 sc gel W/4 sc hulls, plug and 110 sc 50-50

poz cement with 6% total gel. Max. pres. 800 lbs. SI pres. 200 lbs.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Massey
Well Plugging Supervisor

INVOICED

DATE 10/28/68
WV. NO. 8715-U