

15-135-20804-00-00

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

SEP 27 1974

CONSERVATION DIVISION
Wichita, Kansas

09-27-1974

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Chief Drilling Company, Incorporated,

Complete Address 905 Century Plaza, Wichita, Kansas.

Lease Name R.B.B. Well No. 1

Location SE-11W-11W Sec. 23 Twp. 17 Rge. (E) (W) 21

County Ness Total Depth 4102'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling,

Address Box #176, Chase, Kansas. License No. 683

Operation Completed: Hour 12:15 PM Day 21 Month 9 Year 1974

The above well was plugged as follows:

290'--8 5/8" Surface casing, cement circulated with 185 Sx.
4099'--5 3/8" Production casing cemented on bottom with 125 Sx. Top of perforations @
4083'.

Sanded well back to 4050' and set 4 Sx. cement with dump bailer. Pulled 5 3/8" casing
(3000') and squeezed well initially with 3 sacks hulls and 10 sacks gel and followed
with 110 Cu. Ft. cement from 825' to 500' then 5 sacks gel from 500' to 300' and
followed with 30 Cu. Ft. cement from 300' to 225' then 5 sacks gel from 225' to 25'
and finally 10 Cu. Ft. cement from 25' to bottom of cellar. Maximum pump-in pressure-
650#. FSIP--400#. (Mudding and cementing operations by Allied Cmtg., Inc.).

I hereby certify that the above well was plugged as herein stated.

Signed: *M. L. D. [Signature]*
Well Plugging Supervisor

INVOICED
DATE 9/27/74
INV. NO. 9962-117