

15-135-20135-00-00

Form CP-3
Rev. 6-9-67

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 11 1968
CONSERVATION DIVISION
Wichita, Kansas
04-11-1968

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Rains & Williamson Oil Company, Incorporated,
Complete Address 1425 Wichita Plaza, Wichita, Kansas.
Lease Name Brenner Well No. B-1
Location CNW-NE Sec. 20 Twp. 17 Rge. (E) (W) 21
County Ness Total Depth 4300
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Above
Address License No.
Operation Completed: Hour 1:45 PM Day 7 Month 4 Year 1968

The above well was plugged as follows:

537'--8 5/8" Surface pipe, cement circulated with 300 Sx.
Top of Dakota Section @ 525'.
Circulated hole with heavy mud. Pulled DP to 750' and displaced 100 Sx. cement thru
DP from 750' to 425'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement
to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INDEXED
DATE 4/11/68
REV. NO. 7556-w