

15-135-2118-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

DEC 12 1975
12-12-1975
C

Operator's Full Name Theodore I. Leber & Associates
Complete Address 1555 E. 2nd, Wichita, Ks.
Lease Name McCormick Well No. 1
Location NW SW SW Sec. 27 Twp. 17 Rge. (E) (W) 21
County Ness Total Depth 4207'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor DNB Drlg.
Address Wichita, Ks. License No.
Operation Completed: Hour 3:30 A Day 9 Month 12 Year 1975

The above well was plugged as follows:

RTD 4207' 8 5/8 csg set 367' cwc 225 sk. Plg. Mat. 50-50 poz 2 1/2 total gel.
Gunned pits, circulated heavy mud, set 50 sk cmt plug at 500' thru drill pipe.
Heavy mud to 300' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Messer
Well Plugging Supervisor

DATE 12-12-75
INV. NO. 2397-W