

15-135-21473-00-00

P

Form CP-3

KANSAS

REV. 1-1-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

REC-1178
JUN 27 1978
06-27-1978
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15-135-21,473-00-00 (of this well)

Operator's Full Name F & M Oil Co., Inc.

Complete Address 505 Union Center, Wichita, Kansas

Lease Name Irvin Well No. 1

Location NE NW SE Sec. 25 Twp. 17 Rge. (E) (W) 21

County Ness Total Depth 4210'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Woodman-Iannitti

Address Wichita, Kansas License No.

Operation Completed: Hour 6:30 A Day 26 Month 6 Year 1978

The above well was plugged as follows:

RTD 4210' 8 5/8 csg set 468' cwc Flg. Mat. 50-50 poz 2% total gel.

Gunned pits, circulated heavy mud, set 50 sk cmt plug at 550' thru drill pipe.

Heavy mud to 240' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Mussup
Well Plugging Supervisor

DATE 6-28-78
INV. NO. 1582.0