

15-135-20890-00-00

*PK*  
KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
3 24 1975  
CONSERVATION DIVISION  
WICHITA, KANSAS

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Thunderbird Drilling, Inc.  
Complete Address Box 18407, Wichita, Kansas 67218  
Lease Name Stutz "K" Well No. 1  
Location NW NW Sec. 17 Twp. 17 Rge. (E) (W) 25  
County Ness Total Depth 4507'  
Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A         
Other well as hereafter indicated         
Plugging Contractor Knight Casing Pulling  
Address Box 405, Chase, Kansas 67524 License No. 436  
Operation Completed: Hour 10:30 A Day 22 Month 3 Year 1975

The above well was plugged as follows:

Total Depth 4507' 8 5/8 csg set at 263' cwc 200 sk.  
5 1/2 csg set 4501' cw 100 sk cem.  
Filled 5 1/2 csg W/sd (4507-4475) dumped 5 sk cem. W/dump bailer. (4475-4445)  
Cutoff & recovered 2024' of 5 1/2 csg.  
Pumped down 8 5/8 csg with 25 sk gel & water -70 sk poz (50-50) 6% -10 sk gel & water -100 lbs hulls -50 sk poz (50-50) 6% by Allied Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Ben Massey  
Well Plugging Supervisor

DATE 3/26/75  
INV. NO. 1054-W