

15-135-21071-00-00

[Signature]
KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 10 1975

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Patrick Petr. Corp.

Complete Address Suite 414, 200 E. 1st., Wichita, Kansas

Lease Name Shearer Well No. 1

Location W/2 SW NW Sec. 15 Twp. 17 Rge. (E) (W) 25

County Ness Total Depth 4495'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor DNB Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 5 P Day 4 Month 7 Year 1975

The above well was plugged as follows:

RTD 4495' 8 5/8 csg set 280' cwc 160 sk. Flg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 720' thru drill pipe.

Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *Leo Mussey*
Well Plugging Supervisor

INVOICED
DATE 7/14/75
INV. NO. 1616-w